HASSAN DIVISION.

Dated 3rd October 1930.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 3 P.M., on 20th October 1930, for Restoring Mallisettihalli Burudankatte Tank Regd. No. 329 of Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1931.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100, in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Restoring Mallisettihalli Burudankatte Tank Regd. No. 329 of Channarayapatna Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate for Restoring Mallisettihalli Burudanakatte Tank Regd. No. 329 of Channarayapatna Taluk :—

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund at R. L. 55·00.		Rs. a. p.		Rs.
1	Removing anthill and jungle clearing and cutting trenches.	Lump	sum		
2	Removing and refixing old grade stones to required level.	No.		14	
3	Providing and fixing new grade stones ..	,,		4	
4	Painting and figuring the grade stone with white lead and Japan.	,,		18	
5	Providing and fixing top width stones ...	,,		18	
6	Painting Register No. stone	,,		1	
7	Providing and fixing bench mark stones including figuring, carving and painting, etc., complete.	,,		2	
8	Earthwork raising the bund including watering, tamping, cutting grips, etc., complete.	C.yd.		2,940	
9	Turfing to bund for both front and rear slopes	Sq.yd.		4,875	
10	Removing and resetting the old rough stone work.	C.yd.		Lump sum	
11	Providing new rough stone work	,,	Lump	sum	
	Waste Weir.				
12	Extending the natural waste weir by 54 feet with rough stone body wall, etc., complete.	C.yd.	Lump	sum	
	Sluice.				
13	Repairing the sluice	Lump	sum	Rupees	
14	Providing and fixing plug and rod with locking arrangements, etc., complete.	Lump	sum	Rupees	

M. A. SRINIVASACHARI,
Executive Engineer.